high level channel in the State and outside the State ;

(*f*) the length of the low level channel under the Thungabhadra Project ;

(*g*) the length of the said low level channel lying inside the State and outside the State ;

(*h*) the number of acres of land irrigable under the said channel in the State and outside the State ;

(*i*) the number of acres of land for which the irrigation facility has been afforded at present ?

A.—Sri Kadidal MANJAPPA (Minister for Revenue and Public Works).—

(*a*) The quantity of water allowed through the sluices of the Tungabhadra Reservoir varies from season to season according to requirements and there is no uniform rate of issue. However, the maximum discharge for which the Low Level Canal sluices are designed is 2,500 cusecs of which 1,800 cusecs is meant for irrigation.

(*b*) Yes.

(*c*) The High Level canal scheme has not yet been finalised.

(*d*) } Does not arise in view of
(*e*) } reply to (*c*)

(*f*) 225 miles.

(*g*) 106 miles in Mysore limits and 119 miles outside.

(*h*) 92,308 acres have been localised in Mysore State and 1,57,923 acres outside.

(*i*) Field channels have been opened to afford irrigation facilities to an extent of 10,000 acres in Mysore area.

Concreting of Bangalore-Honnavar Road, Tarikere Taluk.

Q.—303. Sri Y. M. CHANDRASEKHARIAH (Kadur).—

Will the Government be pleased to state :—

(*a*) the width, thickness and length of the cement concrete road formed in 146th and 147th miles of Bangalore-Honnavar Road in Tarikere Taluk ;

(*b*) the cost of construction incurred on each cubic foot ;

(*c*) the distance and the quarry from which jelly has been supplied to this concrete road ;

(*d*) the rate paid per yard of this jelly (big size and small size jelly) ;

(*e*) the distance from which sand has been supplied ;

(*f*) the rate paid per yard of this sand ?

A.—Sri Kadidal MANJAPPA (Minister for Revenue and Public Works).—

(*a*) Width 12 feet
Thickness 6 inches
Length 4 furlongs

(*b*) Rs. 1-13-0

(*c*) 18 miles ; Dasarahalli quarry.

(*d*) Rs. 11 per C.yd. for big size jelly (1″ to 1½″) and Rs. 13-14-0 per C.yd., for small size jelly (¾″ to 1″).

(*e*) 15 miles.

(*f*) Rs. 6-8-0 per C.yd.

Concreting Kadur-Mangalore Road near Chickmagalur.

Q.—304. Sri Y. M. CHANDRASEKHARIAH (Kadur).—

Will the Government be pleased to state :—

(*a*) the cost incurred per cubic foot for constructing the cement concrete road at 153rd mile near Chikmagalur in Kadur-Mangalore road ;

(*b*) the number of bags of cement used for every 100 cubic feet of the said concrete road ;

(*c*) the amount spent for one mile of concrete road in the 153rd mile ;

(*d*) the distance from which jell has been supplied to 153rd mile ;

(*e*) the rate paid per yard of th small jelly and big jelly ;

(SRI Y. M. CHANDRASEKHARIAH.)

(*f*) the distance from which sand has been supplied to the said mile ;

(*g*) the rate paid per yard of sand ?

A.—Sri Kadidal MANJAPPA (Minister for Revenue and Public Works).—

(*a*) Rs 1-15-6 per cubic foot on an average.

(*b*) 18¼ bags on the average

(*c*) Rs. 52,000 exclusive of Protective Works.

(*d*) 4 to 5 miles.

(*e*) Rs. 14 per cubic yard for big jelly (¾" to 1" size) and Rs. 16 per cubic yard for small jelly (½" to ¾")

(*f*) 15 miles.

(*g*) Rs. 6-11-0 per cubic yard.

Concreting of Bangalore-Honnavar Road, Bhadravathi Taluk.

Q.—305. Sri Y. M. CHANDRASEKHARIAH (Kadur).—

Will the Government be pleased to state :—

(*a*) the rate paid per foot of concrete road at 155th mile of Bhadravati Taluk in Bangalore-Honnavar Road ;

(*b*) the width and thickness of the said road ;

(*c*) the number of bags of cement used for concreting 100 cubic feet of the said road ;

(*d*) the amount spent on one mile of concrete road in this 155th mile ;

(*e*) the distance from which big and small jelly is supplied to this spot ;

(*f*) the rate paid per yard of this big and small jelly ;

(*g*) the distance from which sand has been supplied to this spot ;

(*h*) the rate paid per yard of this sand ?

A.—Sri Kadidal MANJAPPA (Minister for Revenue and Public Works).—

(*a*) Rs. 1-14-2 per C.ft. inclusive of hire charges of Government machinery.

(*b*) Width of concrete surface 12 feet. Thickness 4½" average.

(*c*) 18¼ bags.

(*d*) Rs. 52,400 exclusive of protective work.

(*e*) 6½ miles.

(*f*) Rs. 12 per Cubic Yard for big jelly.

Rs. 18 per Cubic Yard for small jelly.

(*g*) 4 miles.

(*h*) Rs. 4-8-0 per Cubic yard.

Channels of Lakkavally Projects.

Q.—306. Sri Y. M. CHANDRASEKHARIAH (Kadur).—

Will the Government be pleased to state :—

(*a*) the nomenclature of soils maintained in the right and left bank channels of the Lakkavally Project ;

(*b*) the different kinds of rocks found in the said channels ;

(*c*) the rate paid per yard of these different kinds of soils and rocks ;

(*d*) whether heaps of stones are kept in the places where rocks were found ?

A.—Sri Kadidal MANJAPPA (Minister for Revenue and Public Works).—

(*a*) to (*c*). Please see statement appended.

(*d*) Yes, in cases where it is either necessary for purposes of taking measurements or useful for other works.